Pace Analytical Services, LLC
8 East Tower Circle
Ormond Beach, FL 32174
(386)672-5668

December 19, 2024

Cindy Tomaszewski
City of Cadillac
1121 Plett Rd
Cadillac, MI 49601

RE: Project: UCMR5_SE1_Nov2024
Pace Project No.: 35919999

Dear Cindy Tomaszewski:

Enclosed are the analytical results for sample(s) received by the laboratory on November 19, 2024. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Ormond Beach

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Dmkapadia

DJ Kapadia
dj.kapadia@pacelabs.com
(386)672-5668
Project Manager

Enclosures

Pace Analytical Services, LLC
8 East Tower Circle
Ormond Beach, FL 32174
(386)672-5668

CERTIFICATIONS

Project:	UCMR5_SE1_Nov2024
Pace Project No.:	35919999

Pace Analytical Services Ormond Beach

8 East Tower Circle, Ormond Beach, FL 32174
Alaska DEC- CS/UST/LUST
Alabama Certification #: 41320
California Certification# 3096
Colorado Certification: FL NELAC Reciprocity
Connecticut Certification #: PH-0216
Delaware Certification: FL NELAC Reciprocity
DoD-ANAB #:ADE-3199
Florida Certification #: E83079
Georgia Certification #: 955
Guam Certification: FL NELAC Reciprocity
Hawaii Certification: FL NELAC Reciprocity
Illinois Certification #: 200068
Indiana Certification: FL NELAC Reciprocity
Kansas Certification #: E-10383
Kentucky Certification #: 90050
Louisiana Certification #: FL NELAC Reciprocity
Louisiana Environmental Certificate #: 05007
Maine Certification #: FL01264
Maryland Certification: #346
Massachusetts Certification #: M-FL1264
Michigan Certification #: 9911
Mississippi Certification: FL NELAC Reciprocity
Missouri Certification #: 236
Montana Certification #: Cert 0074
Nebraska Certification: NE-OS-28-14
Nevada Certification: FL NELAC Reciprocity
New Hampshire Certification #: 2958
New Jersey Certification #: FL022
New York Certification #: 11608
North Carolina Environmental Certificate #: 667
North Carolina Certification #: 12710
North Dakota Certification #: R-216
Ohio DEP 87780
Oklahoma Certification #: D9947
Pennsylvania Certification #: 68-00547
Puerto Rico Certification #: FL01264
South Carolina Certification: #96042001
Tennessee Certification #: TN02974
Texas Certification: FL NELAC Reciprocity
US Virgin Islands Certification: FL NELAC Reciprocity
Utah
Utah FL NELAC Reciprocity
Virginia Environmental Certification #: 460165
West Virginia Certification #: 9962C
Wisconsin Certification #: 399079670
Wyoming (EPA Region 8): FL NELAC Reciprocity

Pace Analytical Services, LLC
8 East Tower Circle
Ormond Beach, FL 32174
(386)672-5668

SAMPLE SUMMARY

Project: UCMR5_SE1_Nov2024
Pace Project No.: 35919999

Lab ID	Sample ID	Matrix	Date Collected	Date Received
35919999001	**10413 Crosby Wellfield Service**	Drinking Water	11/18/24 08:04	11/19/24 12:05
35919999002	**FRB-10413 Crosby Wellfield Ser**	Drinking Water	11/18/24 08:01	11/19/24 12:05
35919999003	**12269 44 Road Water Service Bu**	Drinking Water	11/18/24 09:25	11/19/24 12:05
35919999004	**FRB-12269 44 Road Water Servic**	Drinking Water	11/18/24 09:22	11/19/24 12:05

Pace Analytical Services, LLC
8 East Tower Circle
Ormond Beach, FL 32174
(386)672-5668

SAMPLE ANALYTE COUNT

Project: UCMR5_SE1_Nov2024
Pace Project No.: 35919999

Lab ID	Sample ID		Method	Analysts	Analytes Reported	Laboratory
35919999001	**10413**	**Crosby Wellfield Service**	EPA 200.7	ASB	1	PASI-O
			EPA 533	HL	41	PASI-O
			EPA 537.1	TMM1	8	PASI-O
35919999003	**12269**	**44 Road Water Service Bu**	EPA 200.7	ASB	1	PASI-O
			EPA 533	HL	41	PASI-O
			EPA 537.1	TMM1	8	PASI-O

PASI-O = Pace Analytical Services - Ormond Beach

Pace Analytical Services, LLC
8 East Tower Circle
Ormond Beach, FL 32174
(386)672-5668

ANALYTICAL RESULTS

Project: UCMR5_SE1_Nov2024
Pace Project No.: 35919999

Sample: 10413 Service **Crosby Wellfield** **Lab ID: 35919999001** Collected: 11/18/24 08:04 Received: 11/19/24 12:05 Matrix: Drinking Water

Parameters	Results	Units	PQL	MDL	DF	Prepared	Analyzed	CAS No.	Qual
200.7 MET ICP, UCMR	Analytical Method: EPA 200.7 Preparation Method: EPA 200.7 Initial Volume/Weight: 50 mL Final Volume/Weight: 50 mL Pace Analytical Services - Ormond Beach								
Lithium	**7.5 U**	ug/L	22.5	7.5	2.5	11/20/24 04:27	12/03/24 14:57	7439-93-2	N2
533 PFAS Compounds, UCMR	Analytical Method: EPA 533 Preparation Method: EPA 533 Initial Volume/Weight: 272 mL Final Volume/Weight: 1 mL Pace Analytical Services - Ormond Beach								
11Cl-PF3OUdS	**0.0015 U**	ug/L	0.0046	0.0015	1	11/20/24 23:12	11/21/24 17:43	763051-92-9	
4:2 FTS	**0.0009 U**	ug/L	0.0028	0.0009	1	11/20/24 23:12	11/21/24 17:43	757124-72-4	
6:2 FTS	**0.0015 U**	ug/L	0.0046	0.0015	1	11/20/24 23:12	11/21/24 17:43	27619-97-2	
8:2 FTS	**0.0015 U**	ug/L	0.0046	0.0015	1	11/20/24 23:12	11/21/24 17:43	39108-34-4	
9Cl-PF3ONS	**0.0006 U**	ug/L	0.0018	0.0006	1	11/20/24 23:12	11/21/24 17:43	756426-58-1	
ADONA	**0.0009 U**	ug/L	0.0028	0.0009	1	11/20/24 23:12	11/21/24 17:43	919005-14-4	
HFPO-DA	**0.0015 U**	ug/L	0.0046	0.0015	1	11/20/24 23:12	11/21/24 17:43	13252-13-6	
NFDHA	**0.0061 U**	ug/L	0.018	0.0061	1	11/20/24 23:12	11/21/24 17:43	151772-58-6	
PFBS	**0.0009 U**	ug/L	0.0028	0.0009	1	11/20/24 23:12	11/21/24 17:43	375-73-5	
PFDA	**0.0009 U**	ug/L	0.0028	0.0009	1	11/20/24 23:12	11/21/24 17:43	335-76-2	
PFHxA	**0.0009 U**	ug/L	0.0028	0.0009	1	11/20/24 23:12	11/21/24 17:43	307-24-4	
PFBA	**0.0015 U**	ug/L	0.0046	0.0015	1	11/20/24 23:12	11/21/24 17:43	375-22-4	
PFEESA	**0.0009 U**	ug/L	0.0028	0.0009	1	11/20/24 23:12	11/21/24 17:43	113507-82-7	
PFHpS	**0.0009 U**	ug/L	0.0028	0.0009	1	11/20/24 23:12	11/21/24 17:43	375-92-8	
PFMBA	**0.0009 U**	ug/L	0.0028	0.0009	1	11/20/24 23:12	11/21/24 17:43	863090-89-5	
PFMPA	**0.0012 U**	ug/L	0.0037	0.0012	1	11/20/24 23:12	11/21/24 17:43	377-73-1	
PFPeA	**0.0009 U**	ug/L	0.0028	0.0009	1	11/20/24 23:12	11/21/24 17:43	2706-90-3	
PFPeS	**0.0012 U**	ug/L	0.0037	0.0012	1	11/20/24 23:12	11/21/24 17:43	2706-91-4	
PFDoA	**0.0009 U**	ug/L	0.0028	0.0009	1	11/20/24 23:12	11/21/24 17:43	307-55-1	
PFHpA	**0.0009 U**	ug/L	0.0028	0.0009	1	11/20/24 23:12	11/21/24 17:43	375-85-9	
PFHxS	**0.0009 U**	ug/L	0.0028	0.0009	1	11/20/24 23:12	11/21/24 17:43	355-46-4	
PFNA	**0.0012 U**	ug/L	0.0037	0.0012	1	11/20/24 23:12	11/21/24 17:43	375-95-1	
PFOS	**0.0012 U**	ug/L	0.0037	0.0012	1	11/20/24 23:12	11/21/24 17:43	1763-23-1	
PFOA	**0.0012 U**	ug/L	0.0037	0.0012	1	11/20/24 23:12	11/21/24 17:43	335-67-1	
PFUnA	**0.0006 U**	ug/L	0.0018	0.0006	1	11/20/24 23:12	11/21/24 17:43	2058-94-8	
Surrogates									
13C24:2FTS (S)	138	%	50-200		1	11/20/24 23:12	11/21/24 17:43		
13C26:2FTS (S)	123	%	50-200		1	11/20/24 23:12	11/21/24 17:43		
13C28:2FTS (S)	110	%	50-200		1	11/20/24 23:12	11/21/24 17:43		
13C2-PFDoA (S)	84	%	50-200		1	11/20/24 23:12	11/21/24 17:43		
13C3HFPO-DA(S)	102	%	50-200		1	11/20/24 23:12	11/21/24 17:43		
13C3-PFBS (S)	114	%	50-200		1	11/20/24 23:12	11/21/24 17:43		
13C3-PFHxS (S)	115	%	50-200		1	11/20/24 23:12	11/21/24 17:43		
13C4-PFBA (S)	106	%	50-200		1	11/20/24 23:12	11/21/24 17:43		
13C4-PFHpA (S)	101	%	50-200		1	11/20/24 23:12	11/21/24 17:43		
13C5-PFHxA (S)	100	%	50-200		1	11/20/24 23:12	11/21/24 17:43		
13C5-PFPeA (S)	98	%	50-200		1	11/20/24 23:12	11/21/24 17:43		
13C6-PFDA (S)	99	%	50-200		1	11/20/24 23:12	11/21/24 17:43		

Pace Analytical Services, LLC
8 East Tower Circle
Ormond Beach, FL 32174
(386)672-5668

ANALYTICAL RESULTS

Project: UCMR5_SE1_Nov2024
Pace Project No.: 35919999

Sample: 10413 Crosby Wellfield Service **Lab ID: 35919999001** Collected: 11/18/24 08:04 Received: 11/19/24 12:05 Matrix: Drinking Water

Parameters	Results	Units	PQL	MDL	DF	Prepared	Analyzed	CAS No.	Qual
533 PFAS Compounds, UCMR	Analytical Method: EPA 533 Preparation Method: EPA 533 Initial Volume/Weight: 272 mL Final Volume/Weight: 1 mL Pace Analytical Services - Ormond Beach								
Surrogates									
13C7-PFUdA (S)	91	%	50-200		1	11/20/24 23:12	11/21/24 17:43		
13C8-PFOA (S)	102	%	50-200		1	11/20/24 23:12	11/21/24 17:43		
13C8-PFOS (S)	111	%	50-200		1	11/20/24 23:12	11/21/24 17:43		
13C9-PFNA (S)	101	%	50-200		1	11/20/24 23:12	11/21/24 17:43		
537.1 PFAS Compounds, UCMR	Analytical Method: EPA 537.1 Preparation Method: EPA 537.1 Initial Volume/Weight: 253.4 mL Final Volume/Weight: 1 mL Pace Analytical Services - Ormond Beach								
NEtFOSAA	**0.0016 U**	ug/L	0.0059	0.0016	1	11/21/24 17:00	11/24/24 10:25	2991-50-6	
NMeFOSAA	**0.0020 U**	ug/L	0.0059	0.0020	1	11/21/24 17:00	11/24/24 10:25	2355-31-9	
PFTeDA	**0.0026 U**	ug/L	0.0079	0.0026	1	11/21/24 17:00	11/24/24 10:25	376-06-7	
PFTrDA	**0.0023 U**	ug/L	0.0069	0.0023	1	11/21/24 17:00	11/24/24 10:25	72629-94-8	
Surrogates									
13C2-PFDA (S)	80	%	70-130		1	11/21/24 17:00	11/24/24 10:25		
13C2-PFHxA (S)	76	%	70-130		1	11/21/24 17:00	11/24/24 10:25		
NEtFOSAA-d5 (S)	77	%	70-130		1	11/21/24 17:00	11/24/24 10:25		
HFPO-DAS (S)	75	%	70-130		1	11/21/24 17:00	11/24/24 10:25		

Sample: 12269 44 Road Water Service Bu **Lab ID: 35919999003** Collected: 11/18/24 09:25 Received: 11/19/24 12:05 Matrix: Drinking Water

Parameters	Results	Units	PQL	MDL	DF	Prepared	Analyzed	CAS No.	Qual
200.7 MET ICP, UCMR	Analytical Method: EPA 200.7 Preparation Method: EPA 200.7 Initial Volume/Weight: 50 mL Final Volume/Weight: 50 mL Pace Analytical Services - Ormond Beach								
Lithium	**7.5 U**	ug/L	22.5	7.5	2.5	11/20/24 04:27	12/03/24 14:59	7439-93-2	N2
533 PFAS Compounds, UCMR	Analytical Method: EPA 533 Preparation Method: EPA 533 Initial Volume/Weight: 275.57 mL Final Volume/Weight: 1 mL Pace Analytical Services - Ormond Beach								
11Cl-PF3OUdS	**0.0015 U**	ug/L	0.0045	0.0015	1	11/20/24 23:12	11/21/24 17:59	763051-92-9	
4:2 FTS	**0.0009 U**	ug/L	0.0027	0.0009	1	11/20/24 23:12	11/21/24 17:59	757124-72-4	
6:2 FTS	**0.0015 U**	ug/L	0.0045	0.0015	1	11/20/24 23:12	11/21/24 17:59	27619-97-2	
8:2 FTS	**0.0015 U**	ug/L	0.0045	0.0015	1	11/20/24 23:12	11/21/24 17:59	39108-34-4	
9Cl-PF3ONS	**0.0006 U**	ug/L	0.0018	0.0006	1	11/20/24 23:12	11/21/24 17:59	756426-58-1	
ADONA	**0.0009 U**	ug/L	0.0027	0.0009	1	11/20/24 23:12	11/21/24 17:59	919005-14-4	
HFPO-DA	**0.0015 U**	ug/L	0.0045	0.0015	1	11/20/24 23:12	11/21/24 17:59	13252-13-6	
NFDHA	**0.0061 U**	ug/L	0.018	0.0061	1	11/20/24 23:12	11/21/24 17:59	151772-58-6	
PFBS	**0.0009 U**	ug/L	0.0027	0.0009	1	11/20/24 23:12	11/21/24 17:59	375-73-5	

Pace Analytical Services, LLC
8 East Tower Circle
Ormond Beach, FL 32174
(386)672-5668

ANALYTICAL RESULTS

Project: UCMR5_SE1_Nov2024
Pace Project No.: 35919999

Sample: 12269 44 Road Water Service Bu **Lab ID: 35919999003** Collected: 11/18/24 09:25 Received: 11/19/24 12:05 Matrix: Drinking Water

Parameters	Results	Units	PQL	MDL	DF	Prepared	Analyzed	CAS No.	Qual
533 PFAS Compounds, UCMR	Analytical Method: EPA 533 Preparation Method: EPA 533 Initial Volume/Weight: 275.57 mL Final Volume/Weight: 1 mL Pace Analytical Services - Ormond Beach								
PFDA	**0.0009 U**	ug/L	0.0027	0.0009	1	11/20/24 23:12	11/21/24 17:59	335-76-2	
PFHxA	**0.0009 U**	ug/L	0.0027	0.0009	1	11/20/24 23:12	11/21/24 17:59	307-24-4	
PFBA	**0.0015 U**	ug/L	0.0045	0.0015	1	11/20/24 23:12	11/21/24 17:59	375-22-4	
PFEESA	**0.0009 U**	ug/L	0.0027	0.0009	1	11/20/24 23:12	11/21/24 17:59	113507-82-7	
PFHpS	**0.0009 U**	ug/L	0.0027	0.0009	1	11/20/24 23:12	11/21/24 17:59	375-92-8	
PFMBA	**0.0009 U**	ug/L	0.0027	0.0009	1	11/20/24 23:12	11/21/24 17:59	863090-89-5	
PFMPA	**0.0012 U**	ug/L	0.0036	0.0012	1	11/20/24 23:12	11/21/24 17:59	377-73-1	
PFPeA	**0.0009 U**	ug/L	0.0027	0.0009	1	11/20/24 23:12	11/21/24 17:59	2706-90-3	
PFPeS	**0.0012 U**	ug/L	0.0036	0.0012	1	11/20/24 23:12	11/21/24 17:59	2706-91-4	
PFDoA	**0.0009 U**	ug/L	0.0027	0.0009	1	11/20/24 23:12	11/21/24 17:59	307-55-1	
PFHpA	**0.0009 U**	ug/L	0.0027	0.0009	1	11/20/24 23:12	11/21/24 17:59	375-85-9	
PFHxS	**0.0009 U**	ug/L	0.0027	0.0009	1	11/20/24 23:12	11/21/24 17:59	355-46-4	
PFNA	**0.0012 U**	ug/L	0.0036	0.0012	1	11/20/24 23:12	11/21/24 17:59	375-95-1	
PFOS	**0.0012 U**	ug/L	0.0036	0.0012	1	11/20/24 23:12	11/21/24 17:59	1763-23-1	
PFOA	**0.0012 U**	ug/L	0.0036	0.0012	1	11/20/24 23:12	11/21/24 17:59	335-67-1	
PFUnA	**0.0006 U**	ug/L	0.0018	0.0006	1	11/20/24 23:12	11/21/24 17:59	2058-94-8	
Surrogates									
13C24:2FTS (S)	138	%	50-200		1	11/20/24 23:12	11/21/24 17:59		
13C26:2FTS (S)	123	%	50-200		1	11/20/24 23:12	11/21/24 17:59		
13C28:2FTS (S)	113	%	50-200		1	11/20/24 23:12	11/21/24 17:59		
13C2-PFDoA (S)	100	%	50-200		1	11/20/24 23:12	11/21/24 17:59		
13C3HFPO-DA(S)	103	%	50-200		1	11/20/24 23:12	11/21/24 17:59		
13C3-PFBS (S)	114	%	50-200		1	11/20/24 23:12	11/21/24 17:59		
13C3-PFHxS (S)	119	%	50-200		1	11/20/24 23:12	11/21/24 17:59		
13C4-PFBA (S)	108	%	50-200		1	11/20/24 23:12	11/21/24 17:59		
13C4-PFHpA (S)	105	%	50-200		1	11/20/24 23:12	11/21/24 17:59		
13C5-PFHxA (S)	104	%	50-200		1	11/20/24 23:12	11/21/24 17:59		
13C5-PFPeA (S)	102	%	50-200		1	11/20/24 23:12	11/21/24 17:59		
13C6-PFDA (S)	102	%	50-200		1	11/20/24 23:12	11/21/24 17:59		
13C7-PFUdA (S)	102	%	50-200		1	11/20/24 23:12	11/21/24 17:59		
13C8-PFOA (S)	105	%	50-200		1	11/20/24 23:12	11/21/24 17:59		
13C8-PFOS (S)	114	%	50-200		1	11/20/24 23:12	11/21/24 17:59		
13C9-PFNA (S)	104	%	50-200		1	11/20/24 23:12	11/21/24 17:59		
537.1 PFAS Compounds, UCMR	Analytical Method: EPA 537.1 Preparation Method: EPA 537.1 Initial Volume/Weight: 273.13 mL Final Volume/Weight: 1 mL Pace Analytical Services - Ormond Beach								
NEtFOSAA	**0.0015 U**	ug/L	0.0055	0.0015	1	11/21/24 17:00	11/23/24 19:55	2991-50-6	
NMeFOSAA	**0.0018 U**	ug/L	0.0055	0.0018	1	11/21/24 17:00	11/23/24 19:55	2355-31-9	
PFTeDA	**0.0024 U**	ug/L	0.0073	0.0024	1	11/21/24 17:00	11/23/24 19:55	376-06-7	
PFTrDA	**0.0022 U**	ug/L	0.0064	0.0022	1	11/21/24 17:00	11/23/24 19:55	72629-94-8	
Surrogates									
13C2-PFDA (S)	94	%	70-130		1	11/21/24 17:00	11/23/24 19:55		

REPORT OF LABORATORY ANALYSIS

Pace Analytical Services, LLC
8 East Tower Circle
Ormond Beach, FL 32174
(386)672-5668

ANALYTICAL RESULTS

Project:	UCMR5_SE1_Nov2024
Pace Project No.:	35919999

Sample: 12269 44 Road Water Service Bu **Lab ID: 35919999003** Collected: 11/18/24 09:25 Received: 11/19/24 12:05 Matrix: Drinking Water

Parameters	Results	Units	PQL	MDL	DF	Prepared	Analyzed	CAS No.	Qual
537.1 PFAS Compounds, UCMR	Analytical Method: EPA 537.1 Preparation Method: EPA 537.1 Initial Volume/Weight: 273.13 mL Final Volume/Weight: 1 mL Pace Analytical Services - Ormond Beach								
Surrogates									
13C2-PFHxA (S)	90	%	70-130		1	11/21/24 17:00	11/23/24 19:55		
NEtFOSAA-d5 (S)	90	%	70-130		1	11/21/24 17:00	11/23/24 19:55		
HFPO-DAS (S)	81	%	70-130		1	11/21/24 17:00	11/23/24 19:55		

Pace Analytical Services, LLC
8 East Tower Circle
Ormond Beach, FL 32174
(386)672-5668

QUALITY CONTROL DATA

Project: UCMR5_SE1_Nov2024
Pace Project No.: 35919999

QC Batch: 1057703
QC Batch Method: EPA 200.7
Analysis Method: EPA 200.7
Analysis Description: 200.7 MET Drinking Water
Laboratory: Pace Analytical Services - Ormond Beach
Associated Lab Samples: 35919999001, 35919999003

METHOD BLANK: 5812502 Matrix: Drinking Water
Associated Lab Samples: 35919999001, 35919999003

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
Lithium	ug/L	7.5 U	22.5	7.5	12/03/24 13:53	N2

LABORATORY CONTROL SAMPLE: 5812503

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Lithium	ug/L	9	9.2 I	103	50-150	N2

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 5812504 5812505

Parameter	Units	35919122001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Lithium	ug/L	7.5 U	9	9	10.6 I	10.8 I	104	106	0-200		30	N2

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

Pace Analytical Services, LLC
8 East Tower Circle
Ormond Beach, FL 32174
(386)672-5668

QUALITY CONTROL DATA

Project: UCMR5_SE1_Nov2024
Pace Project No.: 35919999

QC Batch: 1058018
QC Batch Method: EPA 533
Analysis Method: EPA 533
Analysis Description: 533 PFAS Compounds, UCMR
Laboratory: Pace Analytical Services - Ormond Beach
Associated Lab Samples: 35919999001, 35919999003

METHOD BLANK: 5814290
Matrix: Drinking Water
Associated Lab Samples: 35919999001, 35919999003

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
11Cl-PF3OUdS	ug/L	0.0017 U	0.0050	0.0017	11/21/24 12:44	
4:2 FTS	ug/L	0.0010 U	0.0030	0.0010	11/21/24 12:44	
6:2 FTS	ug/L	0.0017 U	0.0050	0.0017	11/21/24 12:44	
8:2 FTS	ug/L	0.0017 U	0.0050	0.0017	11/21/24 12:44	
9Cl-PF3ONS	ug/L	0.0007 U	0.0020	0.0007	11/21/24 12:44	
ADONA	ug/L	0.0010 U	0.0030	0.0010	11/21/24 12:44	
HFPO-DA	ug/L	0.0017 U	0.0050	0.0017	11/21/24 12:44	
NFDHA	ug/L	0.0067 U	0.020	0.0067	11/21/24 12:44	
PFBA	ug/L	0.0017 U	0.0050	0.0017	11/21/24 12:44	
PFBS	ug/L	0.0010 U	0.0030	0.0010	11/21/24 12:44	
PFDA	ug/L	0.0010 U	0.0030	0.0010	11/21/24 12:44	
PFDoA	ug/L	0.0010 U	0.0030	0.0010	11/21/24 12:44	
PFEESA	ug/L	0.0010 U	0.0030	0.0010	11/21/24 12:44	
PFHpA	ug/L	0.0010 U	0.0030	0.0010	11/21/24 12:44	
PFHpS	ug/L	0.0010 U	0.0030	0.0010	11/21/24 12:44	
PFHxA	ug/L	0.0010 U	0.0030	0.0010	11/21/24 12:44	
PFHxS	ug/L	0.0010 U	0.0030	0.0010	11/21/24 12:44	
PFMBA	ug/L	0.0010 U	0.0030	0.0010	11/21/24 12:44	
PFMPA	ug/L	0.0013 U	0.0040	0.0013	11/21/24 12:44	
PFNA	ug/L	0.0013 U	0.0040	0.0013	11/21/24 12:44	
PFOA	ug/L	0.0013 U	0.0040	0.0013	11/21/24 12:44	
PFOS	ug/L	0.0013 U	0.0040	0.0013	11/21/24 12:44	
PFPeA	ug/L	0.0010 U	0.0030	0.0010	11/21/24 12:44	
PFPeS	ug/L	0.0013 U	0.0040	0.0013	11/21/24 12:44	
PFUnA	ug/L	0.0007 U	0.0020	0.0007	11/21/24 12:44	
13C2-PFDoA (S)	%	89	50-200		11/21/24 12:44	
13C24:2FTS (S)	%	98	50-200		11/21/24 12:44	
13C26:2FTS (S)	%	99	50-200		11/21/24 12:44	
13C28:2FTS (S)	%	96	50-200		11/21/24 12:44	
13C3-PFBS (S)	%	106	50-200		11/21/24 12:44	
13C3-PFHxS (S)	%	104	50-200		11/21/24 12:44	
13C3HFPO-DA(S)	%	90	50-200		11/21/24 12:44	
13C4-PFBA (S)	%	88	50-200		11/21/24 12:44	
13C4-PFHpA (S)	%	88	50-200		11/21/24 12:44	
13C5-PFHxA (S)	%	88	50-200		11/21/24 12:44	
13C5-PFPeA (S)	%	88	50-200		11/21/24 12:44	
13C6-PFDA (S)	%	85	50-200		11/21/24 12:44	
13C7-PFUdA (S)	%	88	50-200		11/21/24 12:44	
13C8-PFOA (S)	%	87	50-200		11/21/24 12:44	
13C8-PFOS (S)	%	100	50-200		11/21/24 12:44	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

Pace®

Pace Analytical Services, LLC
8 East Tower Circle
Ormond Beach, FL 32174
(386)672-5668

QUALITY CONTROL DATA

Project: UCMR5_SE1_Nov2024
Pace Project No.: 35919999

METHOD BLANK: 5814290 Matrix: Drinking Water
Associated Lab Samples: 35919999001, 35919999003

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
13C9-PFNA (S)	%	84	50-200		11/21/24 12:44	

LABORATORY CONTROL SAMPLE: 5814291

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
11Cl-PF3OUdS	ug/L	0.0019	0.0017 U	80	50-150	
4:2 FTS	ug/L	0.0019	0.0017 I	90	50-150	
6:2 FTS	ug/L	0.0019	0.0017 I	88	50-150	
8:2 FTS	ug/L	0.0019	0.0017 I	90	50-150	
9Cl-PF3ONS	ug/L	0.0019	0.0016 I	84	50-150	
ADONA	ug/L	0.0019	0.0016 I	82	50-150	
HFPO-DA	ug/L	0.002	0.0017 I	86	50-150	
NFDHA	ug/L	0.02	0.021	103	50-150	
PFBA	ug/L	0.002	0.0018 I	90	50-150	
PFBS	ug/L	0.0018	0.0015 I	85	50-150	
PFDA	ug/L	0.002	0.0017 I	83	50-150	
PFDoA	ug/L	0.002	0.0018 I	88	50-150	
PFEESA	ug/L	0.0018	0.0016 I	87	50-150	
PFHpA	ug/L	0.002	0.0018 I	88	50-150	
PFHpS	ug/L	0.0019	0.0017 I	92	50-150	
PFHxA	ug/L	0.002	0.0018 I	88	50-150	
PFHxS	ug/L	0.0018	0.0016 I	91	50-150	
PFMBA	ug/L	0.002	0.0016 I	82	50-150	
PFMPA	ug/L	0.002	0.0017 I	86	50-150	
PFNA	ug/L	0.002	0.0018 I	90	50-150	
PFOA	ug/L	0.002	0.0017 I	86	50-150	
PFOS	ug/L	0.0019	0.0017 I	91	50-150	
PFPeA	ug/L	0.002	0.0018 I	90	50-150	
PFPeS	ug/L	0.0019	0.0017 I	89	50-150	
PFUnA	ug/L	0.002	0.0018 I	92	50-150	
13C2-PFDoA (S)	%			92	50-200	
13C24:2FTS (S)	%			113	50-200	
13C26:2FTS (S)	%			110	50-200	
13C28:2FTS (S)	%			107	50-200	
13C3-PFBS (S)	%			115	50-200	
13C3-PFHxS (S)	%			113	50-200	
13C3HFPO-DA(S)	%			97	50-200	
13C4-PFBA (S)	%			95	50-200	
13C4-PFHpA (S)	%			96	50-200	
13C5-PFHxA (S)	%			95	50-200	
13C5-PFPeA (S)	%			97	50-200	
13C6-PFDA (S)	%			94	50-200	
13C7-PFUdA (S)	%			94	50-200	
13C8-PFOA (S)	%			94	50-200	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

Pace Analytical Services, LLC
8 East Tower Circle
Ormond Beach, FL 32174
(386)672-5668

QUALITY CONTROL DATA

Project: UCMR5_SE1_Nov2024
Pace Project No.: 35919999

LABORATORY CONTROL SAMPLE: 5814291

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
13C8-PFOS (S)	%			112	50-200	
13C9-PFNA (S)	%			93	50-200	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 5814292 5814293

Parameter	Units	35919402001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
11Cl-PF3OUdS	ug/L	0.0017 U	0.019	0.02	0.016	0.018	84	90	70-130	10	30	
4:2 FTS	ug/L	0.0010 U	0.019	0.02	0.016	0.018	84	90	70-130	10	30	
6:2 FTS	ug/L	0.0017 U	0.019	0.02	0.017	0.018	86	90	70-130	7	30	
8:2 FTS	ug/L	0.0017 U	0.019	0.02	0.016	0.018	86	93	70-130	10	30	
9Cl-PF3ONS	ug/L	0.0007 U	0.019	0.02	0.017	0.018	87	92	70-130	8	30	
ADONA	ug/L	0.0010 U	0.019	0.02	0.016	0.018	85	91	70-130	10	30	
HFPO-DA	ug/L	0.0017 U	0.02	0.021	0.018	0.020	90	96	70-130	9	30	
NFDHA	ug/L	0.0067 U	0.2	0.21	0.18	0.21	90	101	70-130	14	30	
PFBA	ug/L	0.0068	0.02	0.021	0.024	0.027	87	96	70-130	9	30	
PFBS	ug/L	0.0021 I	0.018	0.019	0.019	0.019	91	93	70-130	4	30	
PFDA	ug/L	0.0010 U	0.02	0.021	0.018	0.020	87	95	70-130	11	30	
PFDoA	ug/L	0.0010 U	0.02	0.021	0.018	0.019	88	92	70-130	8	30	
PFEESA	ug/L	0.0010 U	0.018	0.019	0.016	0.018	90	97	70-130	11	30	
PFHpA	ug/L	0.0012 I	0.02	0.021	0.019	0.021	89	97	70-130	10	30	
PFHpS	ug/L	0.0010 U	0.019	0.02	0.018	0.019	91	96	70-130	8	30	
PFHxA	ug/L	0.0039	0.02	0.021	0.021	0.024	86	96	70-130	11	30	
PFHxS	ug/L	0.0010 U	0.018	0.019	0.018	0.019	91	96	70-130	7	30	
PFMBA	ug/L	0.0010 U	0.02	0.021	0.018	0.020	89	95	70-130	9	30	
PFMPA	ug/L	0.0013 U	0.02	0.021	0.017	0.018	82	86	70-130	8	30	
PFNA	ug/L	0.0013 U	0.02	0.021	0.018	0.020	89	94	70-130	9	30	
PFOA	ug/L	0.0028 I	0.02	0.021	0.020	0.022	84	93	70-130	11	30	
PFOS	ug/L	0.0014 I	0.019	0.02	0.018	0.019	86	92	70-130	9	30	
PFPeA	ug/L	0.0060	0.02	0.021	0.023	0.025	84	92	70-130	9	30	
PFPeS	ug/L	0.0013 U	0.019	0.02	0.017	0.018	87	93	70-130	9	30	
PFUnA	ug/L	0.0007 U	0.02	0.021	0.018	0.020	88	96	70-130	11	30	
13C2-PFDoA (S)	%						96	88	50-200			
13C24:2FTS (S)	%						166	150	50-200			
13C26:2FTS (S)	%						125	117	50-200			
13C28:2FTS (S)	%						115	109	50-200			
13C3-PFBS (S)	%						122	112	50-200			
13C3-PFHxS (S)	%						126	118	50-200			
13C3HFPO-DA(S)	%						105	100	50-200			
13C4-PFBA (S)	%						116	108	50-200			
13C4-PFHpA (S)	%						112	103	50-200			
13C5-PFHxA (S)	%						111	101	50-200			
13C5-PFPeA (S)	%						102	93	50-200			
13C6-PFDA (S)	%						93	84	50-200			
13C7-PFUdA (S)	%						94	85	50-200			

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

Pace Analytical Services, LLC
8 East Tower Circle
Ormond Beach, FL 32174
(386)672-5668

QUALITY CONTROL DATA

Project: UCMR5_SE1_Nov2024
Pace Project No.: 35919999

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 5814292 5814293

Parameter	Units	35919402001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
13C8-PFOA (S)	%						109	101	50-200			
13C8-PFOS (S)	%						117	109	50-200			
13C9-PFNA (S)	%						101	91	50-200			

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

Pace Analytical Services, LLC
8 East Tower Circle
Ormond Beach, FL 32174
(386)672-5668

QUALITY CONTROL DATA

Project: UCMR5_SE1_Nov2024
Pace Project No.: 35919999

QC Batch: 1058288
QC Batch Method: EPA 537.1
Analysis Method: EPA 537.1
Analysis Description: 537.1 PFOA Compounds, UCMR
Laboratory: Pace Analytical Services - Ormond Beach
Associated Lab Samples: 35919999001, 35919999003

METHOD BLANK: 5815648 Matrix: Water
Associated Lab Samples: 35919999001, 35919999003

Parameter	Units	Blank Result	Reporting Limit	MDL	Analyzed	Qualifiers
NEtFOSAA	ug/L	0.0017 U	0.0060	0.0017	11/23/24 16:00	
NMeFOSAA	ug/L	0.0020 U	0.0060	0.0020	11/23/24 16:00	
PFTeDA	ug/L	0.0027 U	0.0080	0.0027	11/23/24 16:00	
PFTrDA	ug/L	0.0024 U	0.0070	0.0024	11/23/24 16:00	
13C2-PFDA (S)	%	98	70-130		11/23/24 16:00	
13C2-PFHxA (S)	%	93	70-130		11/23/24 16:00	
HFPO-DAS (S)	%	86	70-130		11/23/24 16:00	
NEtFOSAA-d5 (S)	%	96	70-130		11/23/24 16:00	

LABORATORY CONTROL SAMPLE: 5815649

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
NEtFOSAA	ug/L	0.005	0.0041 I	82	50-150	
NMeFOSAA	ug/L	0.006	0.0049 I	82	50-150	
PFTeDA	ug/L	0.008	0.0066 I	83	50-150	
PFTrDA	ug/L	0.007	0.0058 I	83	50-150	
13C2-PFDA (S)	%			96	70-130	
13C2-PFHxA (S)	%			94	70-130	
HFPO-DAS (S)	%			90	70-130	
NEtFOSAA-d5 (S)	%			96	70-130	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 5815650 5815652

Parameter	Units	35920265001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
NEtFOSAA	ug/L	0.0016 U	0.036	0.037	0.032	0.031	87	82	70-130	4	30	
NMeFOSAA	ug/L	0.0019 U	0.044	0.044	0.037	0.035	85	78	70-130	7	30	
PFTeDA	ug/L	0.0025 U	0.058	0.059	0.052	0.049	89	82	70-130	6	30	
PFTrDA	ug/L	0.0022 U	0.051	0.052	0.045	0.043	87	83	70-130	4	30	
13C2-PFDA (S)	%						94	90	70-130			
13C2-PFHxA (S)	%						92	86	70-130			
HFPO-DAS (S)	%						88	81	70-130			
NEtFOSAA-d5 (S)	%						96	90	70-130			

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

Pace Analytical Services, LLC
8 East Tower Circle
Ormond Beach, FL 32174
(386)672-5668

QUALIFIERS

Project: UCMR5_SE1_Nov2024
Pace Project No.: 35919999

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.

ND - Not Detected at or above adjusted reporting limit.

TNTC - Too Numerous To Count

MDL - Adjusted Method Detection Limit.

PQL - Practical Quantitation Limit.

RL - Reporting Limit - The lowest concentration value that meets project requirements for quantitative data with known precision and bias for a specific analyte in a specific matrix.

S - Surrogate

1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.

Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.

LCS(D) - Laboratory Control Sample (Duplicate)

MS(D) - Matrix Spike (Duplicate)

DUP - Sample Duplicate

RPD - Relative Percent Difference

NC - Not Calculable.

SG - Silica Gel - Clean-Up

U - Indicates the compound was analyzed for, but not detected.

N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.

Reported results are not rounded until the final step prior to reporting. Therefore, calculated parameters that are typically reported as "Total" may vary slightly from the sum of the reported component parameters.

Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.

TNI - The NELAC Institute.

ANALYTE QUALIFIERS

I	The reported value is between the laboratory method detection limit and the laboratory practical quantitation limit.
U	Compound was analyzed for but not detected.
N2	The lab does not hold NELAC/TNI accreditation for this parameter but other accreditations/certifications may apply. A complete list of accreditations/certifications is available upon request.

Pace Analytical Services, LLC
8 East Tower Circle
Ormond Beach, FL 32174
(386)672-5668

QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: UCMR5_SE1_Nov2024
Pace Project No.: 35919999

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
35919999001	**10413 Crosby Wellfield Service**	EPA 200.7	1057703	EPA 200.7	1057826
35919999003	**12269 44 Road Water Service Bu**	EPA 200.7	1057703	EPA 200.7	1057826
35919999001	**10413 Crosby Wellfield Service**	EPA 533	1058018	EPA 533	1058074
35919999003	**12269 44 Road Water Service Bu**	EPA 533	1058018	EPA 533	1058074
35919999001	**10413 Crosby Wellfield Service**	EPA 537.1	1058288	EPA 537.1	1058405
35919999003	**12269 44 Road Water Service Bu**	EPA 537.1	1058288	EPA 537.1	1058405

Pace®

Pace® Location Requested (City/State):
Pace Analytical Ormond Beach
8 East Tower Circle, Ormond Beach, FL 32174

CHAIN-OF-CUSTODY Analytical Request Document

Chain-of-Custody is a LEGAL DOCUMENT - Complete all relevant fields

LAB USE ONLY- Affix Workorder/Login Label Here

WO# : 35919999
35919999

Company Name:	City of Cadillac UCMR5	Contact/Report To:	Cindy Tomaszewski
Street Address:	1121 Plett Rd, Cadillac, MI 49601	Phone #:	231-775-2368
		E-Mail:	ctomaszewski@cadillac-mi.net
		Cc E-Mail:	
Customer Project #:			
Project Name:	UCMR5_SE1_Nov2024	Invoice To:	Accounts Payable
		Invoice E-Mail:	lab@cadillac-mi.net
Site Collection Info/Facility ID (as applicable):		Purchase Order # (if applicable):	CAT241104PFL
		Quote #:	
Time Zone Collected: [ ] AK [ ] PT [ ] MT [ ] CT [ ] ET		County / State origin of sample(s):	Michigan

Data Deliverables: [ ] Level II [ ] Level III [ ] Level IV [ ] EQUIS [ ] Other

Regulatory Program (DW, RCRA, etc.) as applicable: Reportable [ ] Yes [ ] No

Rush (Pre-approval required): [ ] Same Day [ ] 1 Day [ ] 2 Day [ ] 3 Day [ ] Other ________

DW PWSID # or WW Permit # as applicable: MI0001030

Date Results Requested: 25 BD TAT

Field Filtered (if applicable): [ ] Yes [X] No

Analysis:

* Matrix Codes (Insert in Matrix box below): Drinking Water (DW), Ground Water (GW), Waste Water (WW), Product (P), Soil/Solid (SS), Oil (OL), Wipe (WF), Tissue (TS), Bioassay (B), Vapor (V), Surface Water (SW),Sediment (SED), Sludge (SL), Caulk (CK), Leachate (LL), Biosolid (BS), Other (OT)

Specify Container Size

Identify Container Preservative Type***

Analysis Requested

Customer Sample ID	Matrix *	Comp / Grab	Composite Start Date	Composite Start Time	Collected or Composite End Date	Collected or Composite End Time	# Cont.	Res. Chlorine Results	Res. Chlorine Units	200.7 MET ICP, UCMR	533 FRB	533 PFAS Compounds, UCMR	537.1 FRB	537.1 PFAS Compounds, UCMR	Sample Comment
10413Crosby Wellfield Service Building	DW	G	—	—	11/18/24	0804	9	—		X		X		X	OQS
FRB-10413Crosby Wellfield Service Building	DW	G	—	—	11/18/24	0801	4	—			X		X		
1226944 Road Water Service Building	DW	G	—	—	11/18/24	0925	6	—		X		X		X	
FRB-1226944 Road Water Service Building	DW	G	—	—	11/18/24	0922	4	—			X		X		

Size: (1) 1L, (2) 500mL, (3) 250mL, (4) 125mL, (5) 100mL, (6) 40mL vial, (7) EnCore, (8) TerraCore, (9) 90mL, (10) Other

*** Preservative Types: (1) None, (2) HNO3, (3) H2SO4, (4) HCl, (5) NaOH, (6) Zn Acetate, (7) NaHSO4, (8) Sod. Thiosulfate, (9) Ascorbic Acid, (10) MeOH, (11) Other

Lab Use Only

Proj. Mgr: **DJ Kapadia**

AcctNum / Client ID:

Table #:

Profile / Template: **20671**

Prelog / Bottle Ord. ID: **EZ 3170184**

Preservation non-conformance identified for sample.

FRB Instructions: Make sure to transfer the provided DI water/PFAS free water into the empty container right at the sampling site (empty container provided looks empty, but it has preservation agent- so **DO NOT** rinse or pour it out). FRBs should not be filled with sample water. FRB should return with ***only one*** filled container/method once completed. **Temperature Requirements:** Sample early in the morning, and prior to shipping, please refrigerate the samples for 4-6 hours immediately after sampling. Overnight samples the same day before 3PM. Ship samples on Monday thru Wednesday only, overnight shipping label included. Samples need to arrive under 10C or will require resampling at cost to client.

Additional Instructions from Pace®:
UCMR5 is for testing finished drinking water ONLY. Please fill containers up to the bottom thread of the container cap and do not flush/overfill the container. Prior to shipping, please refrigerate the samples for 4-6 hours immediately after sampling. Ship samples on Monday thru Wednesday only, overnight shipping label included

Collected By: (Printed Name) CINDY A. TOMASZEWSKI

Signature: CATomaszewski

Customer Remarks / Special Conditions / Possible Hazards:

# Coolers:	Thermometer ID:	Correction Factor (°C):	Obs. Temp. (°C)	Corrected Temp. (°C)	On Ice:
				1.6	

Relinquished by/Company: (Signature)	Date/Time:	Received by/Company: (Signature)	Date/Time:	
CATomaszewski / City of Cadillac	11-18-2024 / 1310	drop off to FedEx		Tracking Number:
Relinquished by/Company: (Signature)	Date/Time:	Received by/Company: (Signature) GAS - PACE	Date/Time: 11.19.24 1205	Delivered by: [ ] In-Person [ ] Courier [ ] FedEX [ ] UPS [ ] Other
Relinquished by/Company: (Signature)	Date/Time:	Received by/Company: (Signature)	Date/Time:	
Relinquished by/Company: (Signature)	Date/Time:	Received by/Company: (Signature)	Date/Time:	Page: 1 of 1

WO#: 35919999
PM: DNK Due Date: 12/27/24
CLIENT: CADIMIUCMR4

Project #
Project Manager:
Client:

Courier: ☑Fed Ex ☐UPS ☐USPS ☐Client ☐Commercial ☐Pace ☐Other:
Tracking # 7474 9866 1977
Custody Seal: ☑Yes ☐No **Seal intact:** ☑Yes ☐No **Ice:** ☑Yes ☐No
Packing Material: ☐Bubble Wrap ☐Bubble Bags ☑None ☐Other

			Comments
Chain of Custody Present	☑Yes	☐No	
Chain of Custody Completed	☑Yes	☐No	
Relinquished & Sampler Signature	☑Yes	☐No	
Samples Arrived within Hold Time	☑Yes	☐No	
Sufficient Volume	☑Yes	☐No	
Correct Containers Used	☑Yes	☐No	
Containers Intact	☑Yes	☐No	
Sample Labels match COC	☐Yes	☑No	533 for 10413 Crosby Well Field Service
Samples received ≤48 hr from collection?	☑Yes	☐No	Building times all bread 0810
If no, were samples kept ≤6°C after 48 hrs of collection?	☐Yes	☐No	
Person contacted for verification			

Temperature Verification

Initials: GAJ Date: 11/12/24 Time: 1757
IR Gun ID: T-426 CF (°C): -0.3

	Observed (°C)	Corrected (°C)	Comments
EPA 533	2.3	2.0	
EPA 537.1	1.9	1.6	

Preservation Verification

pH strip: 234273 pH meter: SN-3
Free Cl Strip/DPD: 241064 Cl Meter: SN-1
200.7 Lab Preserved: Nitric Acid: Date/Time: Initials:

Sample/Container ID	pH 533* (pH 6.0-8.0)	pH 537.1 (pH 6.0-8.0)	pH 200.7 (pH <2)	pH 200.7 Lab Preserved	Free Chlorine** 533	Free Chlorine** 537.1	Comments
10413 Crosby W 1/4	7.1	7.4	<2		ND	ND	
" 2/4	7.3	7.6			ND	ND	
" 3/4	7.3	7.6			ND	ND	
" 4/4	7.3	7.6			ND	ND	
FRB-10413 C	6.7	7.4			ND	ND	
12269 44R 1/3	7.1	7.4	<2		ND	ND	
" 2/3	7.2	7.4			ND	ND	
" 3/3	7.2	—			ND	—	

*533 pH may be adjusted at the bench prior to extraction.
** ND = <0.1 mg/L

Labeled by: GAJ **Reviewed by:** BP **Delivered by:** GAJ

Qualtrax ID: 28060

Pace® Analytical Services, LLC

Preservation Verification Continued

Sample/Container ID	pH				Free Chlorine**		Comments
	533* (pH 6.0-	537.1 (pH 6.0-8.0)	200.7 (pH <2)	200.7 Lab Preserved	533	537.1	
FRB-1226944R	6.6	7.4			ND	ND	

*533 pH may be adjusted at the bench prior to extraction ** ND = <0.1 mg/L